


11 T Dipole Status May 2012


M. Karppinen CERN TE-MSC On behalf of CERN-FNAL collaboration







 Joint development program between CERN and FNAL underway since Oct-2010 to demonstrate the feasibility of Nb3Sn technology for this upgrade by 2014.





11 T Design Challenges



- Iron saturation effects
- Transfer function matching with MB
- Coil magnetization effects
 - Conductor development
 - **Cable development**
- Quench protection
 - Heater development
 - **QPS**

Mechanical structure
Forces almost 2 X MB

Coil fabrication technique

- Reproducibility
- **Handling**
- Thermal
 - Resin impregnated coils

Integration

- Optics
- **Cold-mass**
- **Collimator**
- **Machine systems**



Strand & Cable



11 T DS Dipole Cable and insulation para	meters	unreacted	reacted
Strand (RRP 108/127)			
Strand diameter	(mm)	0.7	0.711
Filament diameter	(µm)	46	46
Cu/non-Cu		1.1	1.1
Jc(4.2K, 12 T)	(A/mm ²)		2730
Degradation	(%)		10
RRR			>200
Cable			
Number of strands		40	40
Trasp. Angle	(deg)	14.5	14.5
Mid-thickness	(mm)	1.269	1.307
Thin edge	(mm)	1.167	1.202
Thick edge	(mm)	1.37	1.411
Width	(mm)	14.70	14.847
Thin edge compaction		0.834	0.846
Thick edge compaction		0.979	0.993
Width compaction		1.020	1.015
Key-stone angle	(deg)	0.79	0.81
Cable Insulation			
Insulation thickness	(mm)	0.150	0.100
Insulation material		E-glass	E-glass



Cable samples made with and without SS core show Ic-degradation well within the initial goal of 10 %.


Cored cable with RRP 151/169 being developed at FNAL.

- Large aspect ratio, low compaction. Presently 20 μm additional compaction
- **FNAL roll the cable in two stages with an intermediate anneal**
- **CERN use single pass process**




11 T Dipole Coil Design





B0(11.85 kA) = 11.21 T



B0(11.85 kA) = 10.86 T

* Coil optimization

- >11 T at 11.85 kA with 20% margin at 1.9 K
- **Field errors below the 10-4 level**


* 6-block design, 56 turns (IL 22, OL 34)

- **14.85-mm-wide 40-strand Rutherford cable, no internal splice**
- **Several X-sections were analyzed with and without core**
- Coil ends optimized for low field harmonics and minimum strain in the cable



Iron Saturation





* Yoke design

- The cut-outs on top of the aperture reduce the *b*3 variation by 4.7 units as compared to a circular shape.
- **The holes in the yoke reduce the** *b***3 variation by 2.4 units.**
- The two holes in the yoke insert reduce the b2 variation from 16 to 12 units.




Transfer Function



* TF of 11 T dipole is different from MB:


- More turns than MB (56 vs. 40) [≠] 11 T dipole is stronger at low field.
- □ More saturation [★] reduction of transfer function at high field.





Coil Magnetization







11 T Dipole Model Program



Date	Description	Length	Remarks	Goals
May-12	1-in-1 Demonstrator Magnet	2 m	Construction at FNAL	Cable technology Coil Technology Quench performance Magnetization effects
Mid-2013	2-in-1 Demonstrator Magnet 1	2 m	FNAL collared coils CM-Assembly at CERN	2-in-1 structure Field quality: - iron saturation
End-2013	2-in-1 Demonstrator Magnet 2	2 m	CERN collared coils CM-Assembly at CERN	- cross-talk - Magnetization effects Quench performance Reproducibility
2014	2-in-1 Prototype Cold Mass	5.5 m	Aperture 1 by FNAL Aperture 2 by CERN CM assembly at CERN	Scale-up Long tooling Fabrication of long coils CM assembly Magnetic performance



11 T Model Dipole Parameters



- FNAL 1-in-1 demonstrator based on existing HFD components. Coils with integrated poles.
- * CERN 1-in-1 model based on CTF (MB). Coils with nonintegrated poles (pole-loading concept).
- * 2 m long 2-in-1 magnets of both concepts.

Parameter	Single-aperture FNAL	Single-aperture CERN	Twin-aperture		
Aperture	60 mm				
Yoke outer diameter	400 mm 🛛 🛛	E 510 mm	550 mm		
Nominal bore field @11.85 kA	10.86 T	11.25 T	11.25 T		
Short-sample bore field at 1.9 K	13.6 T	13.9 T	13.9 T		
Margin B _{nom} /B _{max} at 1.9 K	0.80	0.81	0.81		
Stored energy at 11.85 kA	473 kJ /m	484 kJ /m	969 kJ /m		
F _x per quadrant at 11.85 kA	2.89 MN/m	3.16 MN/m	3.16 MN/m		
F, per quadrant at 11.85 kA	-1.57 MN/m	-1.59 MN/m	-1.59 MN/m		



1-in-1 Demonstrator Mechanical Concept




Coil mechanical support is provided by stainless collars, vertically split iron yoke, aluminium clamp and welded stainless steel skin.

Strong collars and iron yoke create the "rigidity belt" around Nb3Sn coil for conductor protection.

Coil mid-plane and radial shims generate initial coil azimuthal pre-stress at collaring stage.

Skin and clamp tensions deform the iron and produce the desired coil compression. The collar also acts as gap-controller.

Collar-yoke-clamp-skin interfaces are tuned to sustain the horizontal EM force component.






2-in-1 Demonstrator Design



***** Two alternative design concepts




Pole loading design

Integrated pole design



Pole Loading Concept





CERN 2-in-1 Model





FNAL 1-in-1 Demonstrator Status



- * 2 coils completed and fully instrumented with strain gauges and V-taps. CMM revealed dimensional distortions the origin of which is yet to be fully understood. All three coils made so far appear to be similar.
- Spare coil wound from CERN supplied cable has been reacted and is ready for epoxy impregnation.
- Mechanical model of the straight part (about 500 mm) was assembled and used for determining the initial shimming for the Demonstrator.
- Cold mass assembly completed. Electrical connections (splice, instrumentation, heaters) underway
- Magnet test expected as of 4 June.



Coil Fabrication









Wind

24/05/2012

Cure


Reaction





Epoxy impregnation


Instrumentation





Mechanical model 1







- * Mechanical model based on Nb3Sn practice coil (PC-0) instrumented with strain gauges
- Assembly parameters were explored with 5 different sets of shims
- Validation of the assembly tooling and procedure
- Coil and collared coil dimensional control before and after the assembly

MM Measurement Locations (4)







455 mm from RE


552 mm from RE

Before MM

After MM

705 mm from RE

652 mm from RE









* Measured signals from the strain gauges in line with the mechanical model.













FNAL Activities



- Demo test in June
- * 2 lengths of cored RRP 151/169 cable available for 1 m coils.
- Cabling trials in progress to validate single pass process (like CERN).
- Design of 5.5 m long coil fabrication tooling in progress.
- Infrastructure for 5.5 m long coils exists (winding, curing, reaction, impregnation, coil assy, collaring).



FNAL Milestones

- * 1-in-1 Demonstrator test Jun-12
- * 1 m model (cored RRP-151/169)
 - Coil fabrication Jun..Aug-12
 - **Cold mass assembly Nov-12**
 - **Test Dec-12**

* 2-in-1 Demonstrator (2 m)

- Coils for aperture-1 Aug..Oct-12
- 1-in-1 assembly and test Feb-13
- Coils for aperture-2 Nov..Feb-13
- 1-in-1 assembly and test Q2-13
- 2-in-1 assembly and test (@cern) Q3-13
- * 5.5 m prototype magnet
 - Practice coil (Cu) Q2-13
 - Practice coil (Nb3Sn) Q4-13
 - **Coils for aperture-1 & mirror tests Q2-14**
 - Collared coil Q3-14



CERN Design Effort



- * 1-in-1 (2 m) magnet assembly and fabrication drawings being completed.
- * 2-in-1 (2 m) magnet assembly in progress.
- Design of 5.5 m long tooling has begun.
- * Collaring tooling design complete.
- Conceptual design of coil handling and assembly tooling complete. Fabrication design in progress.



Procurement



- Collar laminations for the mechanical model were delivered and inspected in CERN metrology lab. The order for collars for the aperture #1 was raised. Invitation to tender for the supply of collar laminations for aperture #2 to #5 being launched.
- * 1-in-1 yoke laminations ordered.
- ***** Order for the outer shells to raise.
- * ODS copper alloy based wedges (Discup C3/30 material) expected in July.
- Winding tooling completed and commissioned.
- * Curing tooling delivered.
- * Reaction tooling delivered at CERN. Dimensional control underway.
- * Reaction furnace commissioning planned for late July.
- Vacuum impregnation tooling order placed (lead-time 18 w)
- ***** Vacuum impregnation tank expected in August.



CERN Milestones

* Practice coils (2 m)

- Practice coils #1-#2 (Cu) Jun..Aug-12
- Practice coil #3 (ITER Nb3Sn) Aug..Sep-12
- Practice coil #4 (LARP RRP 54/61) Oct..Nov-12
- Mirror test at FNAL Jan-12
- * 2-in-1 Demonstrator (2 m)
 - Coils for aperture-1 (RRP 108/127) Jan...Mar-13
 - 1 1-in-1 assembly and test Q2-13
 - Coils for aperture-2 (PIT) Apr..Jun-13
 - 1-in-1 assembly and test Q3-13
 - 2-in-1 assembly and test Q4-13
- * 5.5 m prototype magnet
 - Practice coil (Cu) Q1-14
 - Practice coil (Nb3Sn) Q2-14
 - **Coils for aperture-1 & mirror tests Q4-14**
 - **Collared coil Q1-15**
 - 2-in-1 cold-mass and cryo-magnet Q2-15
 - Cold test Q3-15